

ANTRIM YACHT CLUB, WHITEHEAD

SECANT WALL



Title: Antrim Yacht Club,
Whitehead

Client: W & R Moore
Construction Ltd.

Engineer: Taylor & Boyd

Description:

This project involved the installation of an 11m long secant piled retaining wall. The secant piles were 600mm in diameter.

Antrim Yacht Club was situated adjacent to a Northern Ireland Railway line. As this site was sensitive a Quinn Piling vibration monitor was installed to monitor vibrations.

All piling work took place at night after the last train has passed on the line.

